



Construction under the Hydraulic Improvements contract includes a new raw wastewater pumping station and appurtenant facilities. The new pumping station houses six 83,000 GPM raw sewage pumps, with 600 million gallon per day capacities. Major piping systems for the project include high and low pressure steam, hydraulic oil, effluent water, and 64" ductile iron and 96" cement lined steel raw sewage piping for the new pumps.

Owner
Metropolitan Water Reclamation District of Greater Chicago

Client
IHC Construction Companies-LLC / FH Paschen

Location
Chicago, IL

Architect/ Engineer
Metcalf & Eddy
AECOM

IMI contract amount
\$13 million

Completion
2010

