



IMI performed the mechanical work on the new pumping station at the airports north detention basin. The station is a wet/dry well arrangement, with (3) 3,500 GPM variable speed pumps and (2) 2,000 GPM low speed pumps. There is also (1) 1,800 gallon/2000 GPM oil/water separator. IMI installed all equipment and piping associated with the project.

**Owner**  
City of Chicago, Dept. of Aviation

**Client**  
Walsh Construction

**Location**  
O'Hare Airport

**Architect**  
CTE/AECOM

**IMI contract amount**  
\$827,000

**Completion**  
January 2009

